

(1) WALLS:- INSULATION IN CAVITY

Ope - Perforated steel lintel
(Dense blockwork)

UI - CTPIR - 1.22 - Rev 3 - Lintel

THERMAL PERFORMANCE

CHECKLIST
(TICK ALL)

ENSURE CAVITYTHERM
CT/PIR IS SECURED FIRMLY
AGAINST INNER LEAF OF
CAVITY WALL

☐

KEYSTONE HI-THERM
INSULATED LINTEL TO BE
USED

☐

Block inner leaf

Unilin Insulation CavityTherm CT/PIR

Block outer leaf

Keystone Hi-Therm Lintel

DPC

Wall tie

Flexible sealant

Drawings are for illustration purpose only - not to scale
Details are based on the acceptable construction details
Refer to S.R. 325 for further guidance on detailing

AIR BARRIER - CONTINUITY

CHECKLIST
(TICK ALL)

☐ SEAL ALL PENETRATIONS
THROUGH AIR BARRIER USING
A FLEXIBLE SEALANT

☐ APPLY FLEXIBLE SEALANT TO
ALL INTERFACES BETWEEN
INTERNAL AIR BARRIER AND
WINDOW/DOOR FRAME
MEMBERS

☐ SEE ACD 1.22 FOR AIR
BARRIER OPTIONS

Copyright © 2026, Unilin Insulation,
All rights reserved

GENERAL NOTES

Keep cavities clean of mortar snots and other debris during construction



CERT No: IAB/TM/01
Thermal Modelers Scheme

CavityTherm CT/PIR mm	110	125	150
Psi Value ψ (W/mK)	0.032	0.038	0.044
Temperature Factor (<i>f</i>)	0.97	0.95	0.95
U-Value Wall (W/m ² K)	0.18	0.16	0.13

To be read in conjunction with the Acceptable Construction Details
Any changes to the above construction may change the calculated values
The U values indicated on this certificate are the actual U values for the proposed construction.
The Psi values are calculated using the modelled U value in accordance with the guidelines set out in
BR497 and ISO 10211. Contact Unilin Insulation technical support for further guidance

Email: tech.ui@unilin.com
Phone No: 046 9066050