

THERMAL PERFORMANCE

CHECKLIST
(TICK ALL)


ENSURE CONTINUITY OF INSULATION THROUGHOUT JUNCTION

ENSURE XTROWALL XO/XW PREFORMED EXTERNAL CORNER BOARD IS SECURED FIRMLY AGAINST INNER LEAF OF CAVITY WALL



AIR BARRIER - CONTINUITY

CHECKLIST
(TICK ALL)



Drawings are for illustration purpose only - not to scale
Details are based on the acceptable construction details
Refer to S.R. 325 for further guidance on detailing

Copyright © *2023, Unilin Insulation,
All rights reserved

GENERAL NOTES

Keep cavities clean of mortar snots and other debris during construction



CERT No: IAB/TM/01
Thermal Modelers Scheme

XtroWall XO/XW	90mm	100mm
Psi Value ψ (W/mK)	0.048	0.045
Temperature Factor (<i>f</i>)	0.95	0.95
U-Value Wall (W/m ² K)	0.18	0.17

To be read in conjunction with the Acceptable Construction Details
Any changes to the above construction may change the calculated values
The U values indicated on this certificate are the actual U values for the proposed construction.
The Psi values are calculated using the modelled U value in accordance with the guidelines set out in BR497 and ISO 10211. Contact Unilin Insulation technical support for further guidance

Email: info.ui@unilin.com
Phone No: 046 9066050